

GENERAL NOTES:

1) ALL METERS DELIVERED MUST BE PACKAGED WITH THE 5' END CAP ATTACHED TO THE ABSOLUTE ENCODER REGISTER. THE END CAP MUST BE ATTACHED IN A SEALED MANNER THAT ALLOWS FULL SUBMERSION OF THE REGISTER WITHOUT MOISTURE PENETRATION. THE ERT MUST BE PREPROGRAMMED FOR IMMEDIATE USE BY UNION COUNTY PUBLIC WORKS.

2) REGISTERS FOR THE VARIOUS TYPES AND SIZES OF METERS SPECIFIED IN THIS CONTRACT MUST ALL BE MAGNETIC DRIVE, 6 DIGIT, GLASS LENS ABSOLUTE ENCODERS, RECORDING IN U.S. GALLONS.

3) ALL NEW METERS IN THESE SIZES MUST HAVE SUBMERSIBLE, GLASS LENS ABSOLUTE ENCODED REGISTERS AND BE PRE-PROGRAMMED WITH THE UNION COUNTY PUBLIC WORKS ROCL ALREADY INSTALLED IN THE ERT.

4) ABSOLUTE ENCODED REGISTER THAT INTERFACES WITH THE ITRON AUTOMATED METER READING ERT (ELECTRONIC RADIO TRANSMITTER) 60W SERIES

5) METER BOX LID TO HAVE AMR LOCATOR (ALLIANCE 1200 OR EQUAL FOR 50W ERT, STANDARD LID FOR 60W ERT)

6) BUILDER/PROPERTY OWNER TO INSTALL NIPPLE, VALVE AND VALVE BOX BEFORE METER WILL BE SET.

